

Govt. Of West Bengal
Office of The Sub-Inspector of Schools
&
Circle Project Co-Ordinator of Asansol Circle
Sukanta Maidan, S.B. Gorai Road
P.O:- Asansol - 3, Dist: - Burdwan (W.B.)



Memo No..08/ASN/SSM/2017

Date:..21/03/2017

Notice Inviting Tender

Sealed Tenders are hereby invited from reputed, bonafied & responsible agencies for **Repairing Grant of Asansol CLRC Office Building** in the District of Burdwan.


Sl No.	Name of the Work	Cost of Tender Paper (DD in favour of "ASANSOL CLRC")	Tender Amount	Completion of Work
1	Repairing Grant of Asansol CLRC Office Building	Rs. 500/-	Rs.3,47,200/-	30 days from the issuing date of Work Order

Tender Document on receipt of application along with Demand Draft of Rs.500/- (Rupees Five hundred) only drawn in favour of "Asansol Circle Level Resource Centre", payable at Asansol as cost of Tender Document (non refundable) will be issued from 21.03.2017 to 12.04.2017 within office hours on any working day from the Office of the undersigned. Application on Company/ Firm/ other Business unit letter head should be addressed to the Circle Project Co-ordinator, Asansol C.L.R.C. (Full Address of the Office to be mentioned with PIN Code).

The last date of sale of Tender Documents is 12.04.2017 up to 5:00 P.M.

The date of Submission of Sealed Tender is up to 13.04.2017, 12:00 Noon and the same will be opened on the that day at 2:00 P.M. at the Office Chamber of CPC, Asansol CLRC, in presence of participants and other officials.

The undersigned reserves the right to accept or reject any or all tenders without assigning any reasons whatsoever and forfeit the Earnest Money in the event of any sort of breach of contract.


CPC, Asansol CLRC
CIRCLE PROJECT CO-ORDINATOR
ASANSOL CLRC
h.r.i.d.

Memo No. 08/ASN/SSM/2017 Dated: 21/03/2017

Copy forwarded for information and circulation:-

1. The Mayor, Asansol Municipal Corporation
2. Sub Division Officer, Asansol Sub-Division.
3. District Project Officer, S.S.M., Bardhaman.
4. ADI(SE), Asansol
5. Office Notice Board


CIRCLE PROJECT CO-ORDINATOR
ASANSOL CLRC
h.r.i.d.

REPARING ESTIMATE OF ASANSOL CLRC

Sl. No.	Description of Item	UNIT	Quantity	Rate (Rs.)	Amount (Rs.)
1	Plaster (to wall, floor etc) with sand and cement mortar including rounding of or chamfering corners as directed and raking out joints or roughing of concrete surface including throating , nosing and drip course where necessary.				
	a) 20 mm th. Plaster with (3:1) sand cement mortar	SQM	353.48	158.00	55849.84
	b) 15mm th. Plaster with (3:1) sand cement mortar	SQM	280.98	138.00	38775.24
	c) 10 mm th. Plaster with (4:1) sand cement mortar	SQM	348	125.00	43500
2	Grey artificial stone in floor , dado , staircase etc. with cement concrete (4:2:1) with stone chips laid in panels as directed with topping made with ordinary / white cement including application of cement slurry before flooring works using @ 1.75 kg / sqm all complete. a) 25mm th.	SQM	210.4	296.00	62278.4
3	Wood work in Door and Window frame fitted and fixed complete including a protective coat of painting at the contact surface of the frame	CUM	0.49	83652.00	40989.48
4	Panel shutter of Door and Window as per Design (each panel consisting of single plank without join) including fitting and fixing the same in position but excluding the cost of hinge and other fittings.a) 35mm th. Shutters with 19mm th. Panel	SQM	19.24	4639.00	89254.36
Total =					330647.32
Additional contingency 5%=					16532.37
Grand Total =					347179.69
Say Rs.=					347180